

SELFRIDGES BIRMINGHAM

PROJECT PROFILE



“ Mansfield Pollard’s modular units were the perfect solution to our efficient on-site build program ”

CHALLENGES:

To provide **eleven air handling units** manufactured, delivered and installed **simultaneously**.

Eight units were needed to service the sales areas and required **stringent temperature and humidity control**. Three units were required to service other areas of the installation including staff rooms and store areas.

Each supply and extract unit was designed to handle **in excess of 16m³/s** and were to be installed and commissioned within a very **demanding timescale**.

OUR SOLUTION:

Our **flexible workforce and premises** allowed all the units to be built simultaneously. Mansfield Pollard's unique **modular build construction** was employed to allow individual sections to be easily **transported and assembled on site**.

Prior to transportation, each unit was **fully tested** in our dedicated facility to eradicate any potential on-site issues.

All on-site installation was undertaken by Mansfield Pollard's **experienced site team** ensuring a smooth and efficient handover.

 **16m³/s SUPPLY & EXTRACT**

 **SIMULTANEOUS DELIVERY & INSTALLATION**

 **ONE COMPANY FROM DESIGN TO COMMISSIONING**


 **100% ON-TIME & ON BUDGET**





AIR HANDLING

Tel : +44 (0)1274 774050

 www.mansfieldpollard.co.uk

 salesteam@mansfieldpollard.co.uk

 Edward House, Parry Lane, Bradford, BD4 8TL